

APPENDIX D

Watershed Restoration Program

**Watershed Assessment
of
Antelope Valley
And
Bear Valley Unnamed Tributary**

Conducted by

USDA Forest Service, Tahoe National Forest
and
Feather River Coordinated Resource Management, Plumas Corporation

February 2008

Watershed Assessment of Antelope Valley and Bear Valley Unnamed Tributary

February 2008

Introduction

An assessment of the hydrologic and erosional conditions of both the Antelope Valley watershed and the adjacent unnamed tributary of the Bear Valley watershed were assessed during the 2007 summer season (Appendix A: Maps). The Antelope Valley Road is a major impact feature that courses through both watersheds. Also assessed was the meadow system of Bear Valley Creek west of the Sierra Brooks Subdivision and a small riparian system near Badenough Creek.

The two primary impacts to watersheds in the Feather River Basin, degraded stream channels and road/stream interactions were the focus of this assessment. These watershed impacts manifest themselves as changes in watershed hydrology and stream channel hydraulics (stream flows, channel connectivity and dimensions) and channel stability (active erosion and sedimentation). Problem areas were documented and ranked in order of stream impacts and restoration needs. Changes to natural stream and riparian morphometry and morphology (stream channel width, depth, slope, pattern, position on the landscape) and the erosion/sedimentation impacts of these features were evaluated. Causal agents were also identified and evaluated to determine their status and potential remedies.

Antelope Valley Watershed

Background and General Condition

The watersheds of Antelope Valley and Bear Valley are located along the southern extent of Sierra Valley and east of the Sierra Nevada mountain range. The streams draining these watersheds flow north into a system of natural and man-made channels within Sierra Valley and eventually drain into the Middle Fork Feather River. Both Antelope Valley and Bear Valley follow northwest trending geologic fractures, or faults.

The predominant rock type making up both watersheds is Tertiary volcanic andesite with intrusions of basalt. The valley bottoms are filled with Quaternary alluvium overlying lake deposits at their downstream ends.

In the Antelope Valley watershed, soil erosion and sedimentation plays a minor role in shaping the watershed. The dominant erosion and transport process is landslide/debris flow, defined as a moving mass of rock fragments, soil, and mud. The material generated by this process covers most of the lower slope areas in the watershed, creating

moderately steep fans of fine to coarse material. These fans also cover portions of the valley bottom alluvium and are so numerous that they form a complex of fans that are practically indistinguishable from one another. Besides being the main source of sediment, they are a primary groundwater recharge zone for Antelope Valley and Sierra Valley.

The stream channels of Antelope Valley are mostly degraded, incised into their original geomorphic features, due to historic and ongoing land use impacts. These impacts include over-grazing and trampling by livestock, logging during different land-use eras, road construction and maintenance, and water diversion and impoundments. Naturally occurring impacts, possibly exacerbated by human impacts, include wildfires, winter and spring floods, floods from summer thunderstorms, and mudflows. The most obvious and direct evidence of watershed change is degradation of stream channels and development of entrenchments (aka gullies) that contain most or all streamflows. Relocation and channelization of streams during the early logging era, construction and relocation of the Antelope Valley Road and construction of Palen Reservoir and the system of diversion ditches (Appendix A: Maps) are the primary cause and effect relationships. Stream channels are still actively down cutting within the entrenchments causing further widening (bank erosion) to take place. The result is continued loss of meadow lands and other landscape features (Appendix B: Photos 1 & 2) plus more rapid draining and loss of groundwater.

The operation of a lumber mill near the center of the watershed in the early 1900s, a roadway located along the main stream channel system, used to transport rough-cut material to a finishing mill near Loyalton, and all roads and skid trails used to transport logs from upper watershed areas to the Antelope Valley Mill have directly and indirectly impacted the watershed. Stream channel morphology and condition were directly impacted and changed during mill operation and its impacts continue today. Besides directly diverting and concentrating streamflows, the road system indirectly changed the hydrologic and general condition of the watershed through changes in the streamflow regime and the production of sediment.

The mill was constructed on the floodplain of Antelope Creek and an unnamed tributary, redirecting and channeling streamflows within the site. The main road, constructed to accommodate a steam tractor used to haul the rough-cut lumber was located down the middle of the main stream system, directly diverting and channeling Antelope Creek. The stream channel incised within its meadow floodplain as a result of these impacts and has resulted in the development of a system of entrenchments that contain stream channels at a lowered (inset) elevation (Appendix C: Diagram 1).

The entire meadow/floodplain system in the lower two thirds of the watershed continues to degrade due to the ongoing impacts from the system of active and abandoned roads. Roads and skid trails constructed to haul trees from upper watershed areas to the mill crossed and/or followed the main Antelope Creek channel and its tributaries with no regard to their water flow conditions. Streams have been diverted from their natural channels and confined to ditches. They no longer utilize their natural floodplains. New

drainage channels were established that rapidly downcut and eroded into their new locations. Ditches were also constructed to manipulate the flow from Antelope Creek for pasture irrigation and the milling operation. Both soil erosion and stream channel degradation were accelerated.

The cumulative effect of degraded stream channels and of the changes to watershed hydrology has been a decrease in the time water stays in the watershed during the wet season and an increase in the frequency of floods. Because of this decrease in wet season water retention, less water is absorbed into soils, rock and meadows, decreasing the amount of water available for release during the dry season.

Antelope Valley Road. This road is having a major impact on the hydrology and morphometry (width, depth, slope, and pattern) of Antelope Valley Creek. It is interrupting and redirecting the natural flow path and flood flow requirements of Antelope Creek and its tributaries. Up valley of Highway 49, the first 1.5 miles of roadway is entrenched into the landscape, intercepts overland flows and redirects that flow to an inside ditch, discharging what was naturally dispersed flows into a few cross-drains of concentrated streamflow. Concentrating streamflows increases the erosion of the affected slopes and discharges sediment directly into Antelope Creek. Concentrating streamflows also means that water leaves the watershed sooner, flood peaks are increased, dry-season streamflows are reduced and the slope below the road dries sooner.

In the upper portions of the watershed, the Antelope Valley Road often interrupts and captures and/or re-directs streamflows from the natural drainage network. Again, slope and channel erosion is increased and down slope areas are de-watered.

Palen Reservoir and Diversion Ditches. Palen Dam (Appendix B: Photo 3) was constructed in 1952 to impound water for irrigation downstream on land owned by Mr. Palen and now owned by the Balderston Family. Material to construct the dam was excavated from the stream channel and floodplain area upstream of the reservoir. Removal of the material has totally disrupted the natural drainage pattern, function and morphometry of the stream channel and has lowered the base elevation of the entire up-valley stream system, inducing further channel degradation in an already degraded system. Extensive and ongoing erosion is evident throughout the affected area.

A bypass ditch was constructed to divert streamflows around the reservoir to provide irrigation water to downstream water users as provided by the 1940 Upper Middle Fork Feather River Water Rights Decree. Before the dam and diversion ditches, water flowed in three natural drainage channels below the existing dam site. Two ditches were constructed in conjunction with the dam in an attempt to reduce flooding during the wet season and to provide irrigation water during the dry season. The natural drainage channels now only carry water during large flood events.

The natural stream channels and meadow floodplains in this lower valley reach have been plowed over but they still exist fundamentally within the lower elevation of the pastures with modified channel morphometry. It appears the ditch on the east side of the valley

does not function and was not used much, if at all. The ditch on the west side of the valley carries most of the water of the Antelope Creek watershed. Portions of this primary ditch were made part of, and interacted with, an unnamed tributary stream channel. The amount of water carried by the ditch during the wet season is greater than its design capacity and, given its constructed design and the erodible nature of the soil material in which it is located; it is unable to function as a stable stream channel. It is degrading in some sections, aggrading in others and widening throughout. Just upstream of Highway 49, water from the ditch is diverted back across the valley to the east and returned to the natural channels before leaving the Balderston Ranch. The location and degradation of this ditch system acts to shunt water around the natural groundwater aquifer of Antelope Valley Creek and to decrease the time water flows through the system, thereby increasing its erosive power and decreasing the amount of water available for groundwater storage.

Conclusion. The natural condition of the Antelope Valley watershed, its vegetation, soils, rock, topography, and drainage system slowed the downslope and downvalley movement of rainwater and snowmelt, maximizing water infiltration and groundwater retention. Large floods were infrequent and when they did occur, damage was probably light to moderate. Summer thunderstorms were localized and erosion from these intense rainstorms was most probably light to moderate. Wildfires were frequent but mostly light. Intense wildfires were very infrequent.

The impacts of human occupation and resource extraction on the watershed counteract the natural tendency of the watershed to slow and absorb water and sediment runoff. Water and sediment now moves through the watershed faster as a result of stream channel degradation and the interception of surface and ground water by the roads and the entrenchments. This faster flow of water is now more concentrated, increasing erosion and sediment transport potentials and increasing peak streamflows (increased frequency of floods). Because many of the stream channels are now located in the bottom of trenches, they are no longer connected to their floodplains. This further exacerbates the concentration of streamflows and the frequency of flooding.

Given the depth of the soils, the fractured rock formations, and the depth of the accumulated soil and rock material, the majority of the water falling on the watershed and not evaporated should be absorbed into the groundwater system. By reducing the amount of time water stays in the watershed, less is absorbed and stored to be released later. Groundwater is the source of most of the water that flows in streams and found in ponds and wetlands. The reduced storage of groundwater translates into reduced streamflows and the amount of other surface water bodies. This is especially noticeable during the summer months because the time when the streams dry is most likely earlier in the year than historically. The height of the groundwater table in relation to the rooting depth of plants is dropping sooner in the year, leading to less water available for non-irrigated plant growth (conversation with Attilio and Jim Ginasi, 2007).

Restoration Potential

The goal for treating the Antelope Valley Watershed is to restore it to proper functioning condition by reducing soil erosion and sediment transport, increasing sediment deposition and storage on naturally occurring depositional features (alluvial fans and meadow/floodplains), reducing flood-flow peaks (increased flood-flow lag times), increasing groundwater retention (raised water tables), and increasing dry-season streamflows (both amount and time).

Although the Antelope Valley Watershed is severely degraded, field reconnaissance surveys indicate that current conditions can be greatly improved through watershed restoration efforts. Much of the detrimental effects from past activities can be reversed or reduced. The objectives for watershed restoration are to:

- Reconnect streams to their remnant channels and historic floodplains.
- Raise groundwater elevations to their historic elevations.
- Reconnect diverted streams to their historic channels.
- Reconstruct roads to minimize their interference with natural runoff patterns.

The most degraded feature is the main Antelope Valley Creek channel. It now resides at the bottom of a ten-foot deep trench that continues to deepen and widen (Appendix B: Photo 4). It has little to no access to its natural floodplain and it continually drains the watershed-long groundwater aquifer. The proposed actions are to obliterate the existing entrenchment and return streamflows to the historic system of remnant stream channels and meadow floodplains. A conceptual-level restoration plan has been developed to obliterate the main Antelope Creek entrenchment from the top of the valley downstream to Palen Reservoir (Appendix B: Maps; Appendix D: Antelope Valley Meadow Restoration Proposal and Cost Estimates). Natural floodplain functions would be restored, including 1) lower flood peaks and frequency (Appendix F: Flood Frequency Analysis), 2) greater groundwater retention and higher groundwater table, 3) vigorous plant growth and expansion of the riparian area, and 4) little to no erosion of the stream system and little to no delivery of sediment downstream.

There are many intermittent and ephemeral tributaries to the main Antelope Valley Creek channel that have either downcut in response to the main channel elevation drop and/or have been diverted from their natural channels due to road or skid trail development (Appendix B: Photo 5). Where streams have been diverted from their natural channels, a second channel has eroded into place. In most cases, the diverted flow of water is concentrated, increasing erosion, speeding the draining of water from the watershed and drying out areas that would otherwise contain riparian vegetation.

A series of ditches were constructed as part of the original timber milling operation to divert water from the upper end of the valley to facilitate mill operations and for irrigation. The constructed ditch system(s) basically had the same effect as the streams

diverted by roads and skid trails. The proposed restoration work would reconnect diverted streams with their natural channels. This action includes closing off existing, unnatural channels created by roads and trails. The result would delay water runoff, allowing it to soak into the ground instead of immediately running off. It would also reduce or eliminate existing soil erosion and re-water dried out meadow and riparian areas.

The current road system has changed the hydrology of the watershed by reducing the time it takes water to drain to the main stream system and out of the watershed. Streamflows are concentrated, increasing erosion and sedimentation potentials and drying out areas below the roads. The proposed restoration actions for the road system would be to reroute and/or re-drain the road system to maintain a more natural drainage pattern (Appendix A: Maps). Specific projects to restore water and sediment flow conditions imposed by roads have only partially been accomplished and needs further surveys. The Antelope Valley Road within the Meadow project reach needs to be addressed as either a complete relocation around the project reach, 1.3 miles, or a complete reconstruction within the project reach with approximately 2000 feet relocated up onto the adjacent slope to move it out of the historic floodplain (Appendix D: Antelope Valley Meadow Restoration Proposal and Cost Estimate).

The lower watershed reach has been severely impacted by the construction of Palen Reservoir and water diversion system. The ditches were constructed to redistribute water from the reservoir and to divert water around the reservoir. The reservoir was constructed using dozers to move soil material from the upstream meadow area to the dam site. The floodplain has been almost completely eliminated in the excavated area and a 10-foot drop was created in the valley that lowered the base level for the entire valley upstream and resulted in renewed headcutting and gully development upstream (Appendix B: Photo 6). Restoration of the watershed does not include removal of the Palen Dam and Reservoir. A functioning wetland has developed that includes open water and near shore, shallow wetland and riparian habitats.

The water-works that diverts water around Palen Reservoir consists of a diversion structure (Appendix B: Photo 7) located approximately 2500 feet upstream of the reservoir and a ditch from the diversion works to the main Antelope Valley Creek ditch approximately 900 feet downstream of Palen Reservoir outlet. Palen Reservoir and dam is an obstruction to natural streamflows and the upstream diversion works and spillway structure has not functioned as designed for many years. Even though water is no longer diverted into the ditch, it intercepts a significant amount of water from the adjacent hill slope causing continued erosion of the ditch as it drains back to the main channel (Appendix B: Photos 8 & 9). The proposed restoration action would remove the small diversion structure and ditch and restore natural stream and hill slope processes.

Unnamed Tributary to Bear Valley Creek

Background and General Condition

The history of this tributary watershed of Bear Valley Creek (Appendix A: Maps) includes logging, livestock grazing, road construction, and wildfires, including the Cottonwood Fire that burned as recently as 1994. The most obvious changes to what was a properly functioning watershed are poorly drained and located roads, especially the Antelope Valley Road, and the development of a discontinuous gully system along the main-stem stream channel.

Roads in this nearly 4 square mile watershed capture water flowing in small stream channels and from springs and seeps, directing and concentrating water in roadside ditches, releasing the water down slope where the roadside ditch encounters another stream channel. This overburdens that stream and causes it to adjust by accelerating the erosion and sedimentation process. Some road segments are so poorly located that they cannot drain or drain slowly, creating road segments that are easily damaged by traffic during wet conditions. Other road segments drain directly into the adjacent main stem stream channel, dumping an extra load of water and sediment.

A discontinuous gully system (one that begins and ends several times along the course of the channel) has developed along the main stem of this unnamed Bear Valley tributary stream, primarily along the upper and middle reaches. The discontinuous gully development is an indication that the system is out of balance and struggling to adjust to the hydrologic and riparian changes that have been imposed on it.

It appears that the nearly complete burn that occurred as a result of the Cottonwood Fire has caused an increase in streamflows and a loss of channel stability. The primary stabilizing component of this stream system is vegetation, both from the roots and stems of live plants and from dead plant pieces forming jams within the channel. The stream is now attempting to downcut, but there's much more sediment in the system to be transported than there is streamflow (stream power) to move it. Log jams have formed within the channel system as burned trees have decayed and fallen to the ground and into the stream. The jams that have formed within the channel are slowing the channel degradation process, contributing to its discontinuous nature and eventually to the stability of the channel.

In addition to the effects of the roads and burn, water was diverted at several locations, especially along the lower reach where the stream merges with the Bear Valley Creek system. These diversions were apparently for irrigation and as a result of road location and construction.

Restoration Potential

Because the Antelope Valley Road intercepts most of the surface water flowing to it and carries that flow in roadside ditches and on the road surface itself, water flows are

concentrated, erosion and sedimentation problems are increased, and down slope areas are dewatered. The restoration action proposes to reconnect all natural drainage channels, eliminate roadside ditches and out-slope road surfaces. Specific projects have not been identified and needs further surveying to develop.

The main stream channel contains several degrading sections and several sections where the stream has been diverted. The restoration action proposes to obliterate the severely degraded stream sections and remove the stream diversions, reconnecting these stream sections to their natural channels and floodplains. Like the roads, specific projects are yet to be identified and developed. The primary exception is downstream of the stream crossing immediately adjacent to Bear Valley Meadow. This section of the stream channel is included in the Bear Valley Meadow restoration proposal, below.

Bear Valley Creek Meadow

The Bear Valley Creek Meadow (Appendix A: Maps; Appendix G: Bear Valley Meadow Surveys) is severely degraded, forming a system of actively eroding entrenchments (aka, gullies) that measure 2 to 15-feet deep and 10 to 100-feet wide (Appendix B: Photo 10). The stream system is now confined to the entrenchments and generally cannot overbank onto the historic floodplain. Groundwater drains rapidly, leaving little to augment summer streamflows and causing a dramatic change in the composition and diversity of the meadow vegetation. The degradation of the system extends the entire length of the meadow and into the upstream canyon reach, where it connects with the rapid runoff and high sediment load of that reach.

Additionally, there is a third entrenched stream system that involves shorter sections of the meadow. The ability for streamflows to frequently access floodplain areas has been almost completely eliminated as the stream channel continues to degrade into the deep alluvial soils of the meadow/floodplain complex. Because the entrenched stream system concentrates runoff and continues to actively erode its bottom and banks, it contributes significantly to the increased frequency of flooding and the high sediment loads of Smithneck Creek, directly affecting stream channel stability upstream and through the town of Loyalton.

Although it is a complicated system, the meadow can be restored to properly functioning condition. The action proposed is to obliterate the entire system of entrenchments and to re-establish streamflows to the system of channels and floodplains located on the surface of the meadow. These channels are remnants of the historic stream system prior to the degraded system we see today.

The goals of the project are to improve aquatic and riparian habitats (improve quality and increase amount), to improve conditions of water flow (reduce flood peaks and increase late season flows downstream of the project reach), and to improve water quality (reduce sediment loads, nutrient loads and summer water temperature). Project objectives are to restore the historic streamflow, floodplain, and sediment-trapping functions of the

meadow, and to restore the functional attributes of the historic, unconfined aquifer by obliterating the entrenchments and by spreading streamflows onto the meadow.

A draft design has been developed that treats approximately 8000-feet (1.5 miles) of valley length by obliterating the system of entrenchments with approximately 66 soil plugs that would return the groundwater surface (water-table) to near, or at, the meadow surface (Appendix A: Maps; Appendix E: Bear Valley Meadow Restoration Proposal and Cost Estimates). This groundwater surface would be exposed in a series of ponds between the soil plugs. Ponds would form where entrenchment/meadow areas are excavated to supply soil for the construction of the plugs. The functions of the floodplains would be restored, including reducing the effects of floods (Appendix F: Flood Frequency Analysis), improving groundwater retention and raising the groundwater table and providing for vigorous plant growth, thereby expanding the riparian area, and eliminating the ongoing erosion of the main channel.

A large, well vegetated soil and rock grade-control/channel-drop structure (Appendix C: Diagrams and Charts) would be constructed at the downstream end of the project, immediately upstream of the Sierra Brooks Drive stream crossing (Appendix B: Photo 11), to support the entire project at its historic meadow elevation and to drop streamflows approximately 10-feet (total elevation difference) to the bottom of the gully before it flows through the crossing culvert. The structure would be about 300-feet long. The culvert and its boulder grade-control (located at the culvert outlet) would support the toe of the grade-drop structure.

Badenaugh Creek Area

One small meadow area on the lower end of the Badenaugh Road just above the Smithneck Creek Road (Appendix A: Maps) has been degraded by the diversion of streamflows to a small swale unable to handle the additional water. The diverted stream is primarily fed by springs located on the adjacent hillside. The diversion is caused by an old railroad grade located at the top of the meadow. The area has been further degraded by a road that is located within the stream-riparian zone and that crosses it. The road is severely rutted, channeling and concentrating water into the meadow, causing gullies to form. The restoration action proposes to reconnect the natural system of channels by obliterating the railroad grade, relocating the road out of the meadow and onto the hill slope to the south, and revegetating the obliterated areas.

Impact Avoidance and Minimization Measures

Although all of the restoration actions are proposed with the goal of improving the long-term ecological conditions of the watersheds, construction activities necessary to these restoration actions may have a potential of causing short-term impacts to natural resources such as water quality and wildlife habitat. Therefore, impact avoidance and minimization measures described in Appendix H will be implemented as part of the proposed restoration actions described above.

Discussion of Gully Obliteration Using the “Plug-and-Pond” Restoration Technique:

Gully obliteration is the only known method for restoring all the hydrologic and geomorphic functions of a meadow. Streamflows are restored to their historically unconfined position on the meadow surface where flow depths, velocities, shear stresses and stream power are low. The surface of the meadow becomes highly resistant to erosion due to vigorous plant growth watered by a shallow groundwater table. The restored stream no longer transports high sediment loads because upstream loads are captured at the top of the meadow and the actively eroding gully has been eliminated. Gully obliteration using the “plug-and-pond” technique has been found to be much less expensive than applying other treatments. Treatments such as check-dams have been estimated to cost more than ten times what it costs to obliterate gullies as here described. The use of check dams has been found to not restore meadows and their maintenance is usually very long-term.

It is more difficult and costly to implement restoration treatments in the confinement of a gully. Treatments used to stabilize a gully do not significantly reduce stream power, but rather redirects it. More rock placement and immediate revegetation work is required, increasing costs significantly. The degraded system is not restored but rather temporarily stabilized in its existing state. This stability is usually tentative because the treatments are subject to high streamflow forces, are at high risk of damage and, therefore, long-term maintenance. Erosion and sediment from the eroding entrenchment is significantly reduced, but flood frequencies and summer low flows leaving the project reach are not altered. Sediment from upstream sources can be captured within the gully, but this is usually insignificant as compared to the amount eroding from the gully itself.

To not treat a degraded meadow is to allow it to continue to degrade and widen. It will continue to do so until most or all of the meadow is removed to the elevation of the newly forming stream channel. A new stream channel and floodplain system is established at the lowered elevation. Groundwater is not captured and stored along this reach. Flood flows are again attenuated, but summer low flows are not enhanced by the captured groundwater. Sediment from upstream sources continues to influence the stability of the stream channel, but deposition in the upstream sections and, possibly throughout the untreated reach begins to raise the meadow. It has been estimated that it could take 500⁺ years for the stream and its floodplain to reach this state and several thousand more years to refill the meadow to where it was prior to the latest episode of degradation.

Gully obliteration (Appendix C: Diagram 2) is the primary restoration technique recommended where the stream has degraded into a meadow formed by accumulated alluvial soils and no constraints such as houses are present. Because it is usually not economical or practical to completely fill the gully with soil, a series of soil plugs are instead constructed that are strategically placed and filled to the level of the adjoining meadow surfaces or slightly higher (Appendix B: Photo 12). Because the cost of importing soil usually renders the project very expensive or uneconomical, fill material is

obtained on site by excavating the sides and bottom of the gully between the plugs. The excavated sections become filled with water as the groundwater in the meadow rises.

While an excavator is used to excavate the soil material, plug construction, including compaction, is accomplished using a rubber-tired loader. Topsoil is removed and set aside before pond excavation and then placed on the plugs to aid the revegetation effort. Wetland plant species are used to vegetate the plugs because the elevation of the finished plugs is generally at or slightly higher than the surrounding meadow. The plugs and ponds become part of the meadow floodplain and are able to absorb and spread water flows. The ponds rise and fall with the movement of floodwater through the restored meadow, reducing stream power, recharging groundwater, and reducing flood peaks (Appendix B: Photo 13).

The four primary benefits to this type of restoration are:

1. A raised groundwater table and vigorous plant growth (Appendix C: Chart 1).
2. A wide floodplain with frequent overbank flows that reduce flood peaks (Appendix C: Chart 2) and recharge groundwater.
3. Increased summer flows, especially downstream of the project (Appendix C: Chart 3).
4. Improved water quality and wetland habitats.

Restoring these processes and components re-invigorates the entire meadow ecosystem and adjacent upland areas. The effects can be realized throughout the watershed, on-site, upstream and downstream.

Summary of Watershed improvement Projects

Antelope Valley Watershed

1. Obliterate the main gully and reinstall the stream to the meadow surface.
2. Reconnect natural drainage channels that have been diverted or relocated by past activities and by roads. Obliterate road and skid trail water flow interceptions, water diversion ditches, and the gullies that have formed.
3. Obliterate the Palen Reservoir bypass diversion dam and ditch.

Unnamed Tributary to Bear Valley Creek

1. Reconstruct the Antelope Valley Road to reconnect all drainage channels and outslope the road surface.
2. Reconnect diverted streamflows to their natural drainage channels and obliterate the diversion channels.
3. Include the lower portion of the stream and meadow system in the larger Bear Valley Meadow restoration project.

Bear Valley Creek Meadow


1. Obliterate the gully system and return the streamflows to the meadow surface, restoring groundwater conditions.

Badenaugh Road Area

1. Remove the railroad grade and return water flows to the natural channel.
2. Relocate the road out of meadow (obliterating the existing road) and repair the degraded stream channels.

APPENDIX A

MAPS



Antelope Valley Restoration Project
Antelope Valley Watershed
Tahoe National Forest
Sierraville Ranger District
In Partnership with:
CA Wildlife Foundation
&
CA Department of Fish and Game
North Central Region

Perennial Stream Restoration


- Current Main Channel
- Restoration Channel
- Proposed Pond

Seasonal Stream Restoration

- Seasonal Channel
- Seasonal Re-route Channel
- Channel Closure
- Overland Flow
- diversion ditch (remove)
- Cross Drain (needed)

Road Restoration

- Improved Road
- Local/Dirt Road
- Road Segment Removal



Map created by B. Spear
Hydrologic Tech
07/31/2007

Antelope Valley Restoration Project

Antelope Valley Watershed

Tahoe National Forest

Sierraville Ranger District

In Partnership with:

CA Wildlife Foundation

&

CA Department of Fish and Game

North Central Region

Trimble GPS Features

- Perennial Stream
- Perennial Channel Closure
- Perennial Reroute
- Seasonal Drainage
- Seasonal Channel Closure
- Seasonal Reroute

Restoration Work

- Overland Flow
- Grade Drop Structure
- Log Jam
- Road Segment Removal
- Cross Drain (needed)


Road

- Antelope Valley Rd
- Remnant Rd Bed/Degraded Rd

0 750 1,500 Feet




Map created by B. Spear
Hydrologic Tech
08/16/2007











Antelope Valley Watershed Analysis

Tahoe National Forest
Sierraville Ranger District

February 28, 2008

 Analysis Area Boundary

GPS Features

-  Existing Flow
-  Proposed Flow
-  Small Drainages
-  Obliterate Ditch
-  Abandoned Rd Grade
-  Road
-  Entrenched Road
-  Meadow



Prepared by SH
East Zone GIS

Antelope Creek

Loyalton

Palen Reservoir


Bear Valley Creek

Bear Valley Creek Analysis Area

Badenaugh
Analysis Area

Antelope Valley Watershed

Unnamed Tributary to Bear Valley Creek Watershed




Bear Valley Restoration Project
Bear Valley Watershed
Tahoe National Forest
Sierraville Ranger District
February 28, 2008

GPS Features

- Perennial Channel
- Seasonal Channel
- Proposed Flow
- Proposed Plug
- Grade Drop Stucture
- Cross Section
- Obliterate Ditch
- Obliterate Road

Prepared by SH,
East Zone GIS



APPENDIX B
PHOTOGRAPHS

Photo 1



Vertical Bank of the Antelope Creek Entrenchment

Photo 2



Antelope Valley Entrenchment

Photo 3



Palen Dam and Reservoir

Photo 4



The Eroding Bottom and Banks of Antelope Valley Creek

Photo 5



Tributary Stream Channel Caught in the Antelope Valley Road
Inside Ditch

Photo 6



The Top of The Area Excavated to Supply Material For Palen Dam
Note Dewatering of the Meadow Above and the Sudden Drop in the Valley

Photo 7



Palen Reservoir Bypass Diversion Dam
Note Its Deteriorated State

Photo 8



Failing Outlet Channel of Palen Reservoir

Photo 9



West-side Ditch and Antelope Valley Creek

Photo 10




Bear Valley Creek at the Bottom of an Entrenchment
Note No Floodplain so Erosion Forces Against Banks is High

Photo 11



Bear Valley Creek Immediately Upstream of Sierra Brooks Drive

Photo 12



Section of the Last Chance Creek Gully Obliterated Using the Plug-and-Pond Technique (*Note, Late Summer Conditions in this Seasonal Streamflow Section*)

Photo 13




Remnant Channel Streamflow and Flooding onto the Historic Floodplain
Humbug Creek Upstream of Delleker on the Michelson Ranch


APPENDIX C

DIAGRAMS AND CHARTS


Diagram 1



Succession of States of Degradation of the Antelope Valley Creek
And Entrenchment Development



GULLIED MEADOW WITH LOWERED WATER TABLE




RESTORED MEADOW WITH RAISED WATER TABLE


Cross-sections Through a Typical Degraded and Restored Valley

GRADE-CONTROL AND CHANNEL-DROP STRUCTURE


PROFILE VIEW



CROSS-SECTION VIEW




PLAN VIEW




Clarks Creek Restoration Project, 8/2001
Seasonal Groundwater Change
(ave. 1998-2007)

CHART 1




Big Flat Discharge, WY 2006 Annual Hydrograph

CHART 2



Big Flat Discharge, WY 2006 Spring Recession

CHART 3



APPENDIX D
ANTELOPE VALLEY MEADOW
RESTORATION PROPOSAL
AND
COST ESTIMATES

ANTELOPE VALLEY MEADOW RESTORATION PROPOSAL COST ESTIMATES

Feb-08

Work Item	Estimated Cost
Field Work & Site Surveys	\$8,000.00
NEPA/CEQA	\$0.00
Permit Acquisition	\$5,000.00
Project Design & Engineering	\$15,000.00
Contract Preparation	\$1,000.00
Contract Administration	\$14,000.00
Contract Cost	\$525,000.00
Materials & Supplies	\$1,000.00
Monitoring	\$3,000.00
Total	\$572,000.00

ANTELOPE VALLEY MEADOW RESTORATION PROPOSAL AND COST ESTIMATES

Feb-08

Meadow Restoration Cost Estimate

Bear Valley Project Length (ft)	8000
Total Cost w/rock	\$400,000
Total Cost per foot	\$50
Cost w/o rock	\$275,000
Cost per foot	\$34
Antelope Valley Project Length (ft)	9000
Total Cost @ \$50/ft	\$450,000
Total Cost @ \$34/ft	\$309,375

Antelope Valley Road Relocation Cost Estimate

Length of Relocated Rd (mi)	1.3
Length of Reconstructed Rd (mi)	1.8
Number of Xings	6
Cost to reconstruct @ \$5,000/mi	\$9,000
Cost to obliterate @ \$2,000/mi	\$2,600
Total	\$11,600

Antelope Valley Road Reconstruction Cost Estimate

Length of Reconstructed Rd (mi)	1.3
Number of Xings	4
Length of Rd to Relocate	0.4
Number of Xings	1
Cost to reconstruct @ \$5,000/mi	\$4,500
Cost to relocate @ \$15,000/mi	\$6,000
Total	\$10,500

Palen Reservoir Bypass Ditch Obliteration

Length of Ditch (ft)	3,960
Average Ditch Width (ft)	15
Average Ditch Depth (ft)	5
Volume (yd ³)	11,000
Days @ 1200 yd ³ /day	9
hours	73
Cost @ \$200/hr	\$14,667

Estimated Total Construction Cost = \$476,267 X1.1= **\$523,893**

ANTELOPE VALLEY MEADOW RESTORATION PROPOSAL AND COST ESTIMATES

Feb-08

Engineering Surveys

Estimated Number of XSs	30
Survey Days @ 3 XSs/day	10
Long Profile @ 4500'/day	2
Total Survey Days	12
Total Survey Hours	96
Cost @ \$50/hour	\$4,800
Travel @ 120/day (mi)	1440
Travel @ 0.55/mi	\$792
Data Development (hrs)	40
Cost @ \$50/hour	\$2,000
Total Cost	\$7,592

Engineering Design and Layout

Estimated Number of Plugs	75
Number of Plug Layouts/day	6
Number of Days to Layout	13
Number of Ponds	75
Number of Pond Layouts/day	6
Number of Days to Layout	13
Total Layout Days	25
Total Layout Hours	200
Cost @ \$50/hour	\$10,000
Travel @ 120/day (mi)	3000
Travel @ 0.55/mi	\$1,650
Data Development (hrs)	40
Cost @ \$50/hour	\$2,000
Total Cost	\$13,650

Estimated Total Cost **\$21,242**

Construction Oversight

Estimated Construction Days	35
Hours	280
Cost @ \$50/hour	\$14,000

APPENDIX E
BEAR VALLEY MEADOW
RESTORATION PROPOSAL
AND
COST ESTIMATES

BEAR VALLEY CREEK GULLY OBLITERATION PROPOSAL												
Gully Obliteration												
Plug_ID	Perimeter (ft)	Area (ft ²)	Acres	Hectares	Average Depth (ft)	Est. Vol. (ft ³)	Vol. X 1.2	Vol. (yd ³)				
1A	48.09	141.24	0.0032	0.0013	1.7	240	288	11				
1B	157.00	1313.30	0.0301	0.0122	1.5	1,970	2364	88				
1C	47.70	135.94	0.0031	0.0013	4.0	544	653	24				
1	158.39	1542.29	0.0354	0.0143		0	0	0				
2	126.40	915.58	0.0210	0.0085	2.0	1,831	2197	81				
3	141.82	1160.68	0.0266	0.0108	2.5	2,902	3482	129				
4	166.11	1605.50	0.0369	0.0149	2.5	4,014	4817	178				
5	146.56	1198.53	0.0275	0.0111	3.0	3,596	4315	160				
6	159.09	1530.71	0.0351	0.0142	2.0	3,061	3674	136				
7	220.87	2804.66	0.0644	0.0261	2.0	5,609	6731	249				
8	59.22	198.19	0.0045	0.0018	2.0	396	476	18				
9	87.60	395.80	0.0091	0.0037	3.0	1,187	1425	53				
10	149.10	1354.93	0.0311	0.0126	3.0	4,065	4878	181				
11	215.48	2588.39	0.0594	0.0240	2.0	5,177	6212	230				
12	72.44	298.59	0.0069	0.0028	2.0	597	717	27				
13	111.48	725.92	0.0167	0.0067	2.5	1,815	2178	81				
14	97.30	526.48	0.0121	0.0049	2.5	1,316	1579	58				
15	152.56	1337.91	0.0307	0.0124	2.0	2,676	3211	119				
16	54.48	176.75	0.0041	0.0016	3.0	530	636	24				
17	54.54	157.86	0.0036	0.0015	4.0	631	758	28				
18	84.67	345.43	0.0079	0.0032	2.5	864	1036	38				
19	117.18	703.50	0.0162	0.0065	3.0	2,110	2533	94				
20	301.47	3705.83	0.0851	0.0344	3.0	11,118	13341	494				
21	245.77	3028.00	0.0695	0.0281	3.0	9,084	10901	404				
22	146.63	1310.54	0.0301	0.0122	1.5	1,966	2359	87				
23	171.04	1786.94	0.0410	0.0166	3.0	5,361	6433	238				
24	333.18	5765.93	0.1324	0.0536	4.0	23,064	27676	1,025				
25	225.51	2969.25	0.0682	0.0276	5.0	14,846	17816	660				
26	210.10	2668.80	0.0613	0.0248	2.0	5,338	6405	237				
27	239.55	2217.81	0.0509	0.0206	3.5	7,762	9315	345				
28	47.40	118.12	0.0027	0.0011	1.5	177	213	8				
29	226.40	2402.08	0.0551	0.0223	2.5	6,005	7206	267				
30	156.68	1372.76	0.0315	0.0128	4.0	5,491	6589	244				
31	108.10	693.34	0.0159	0.0064	2.5	1,733	2080	77				
32	280.13	4066.32	0.0933	0.0378	2.5	10,166	12199	452				
33	173.33	1811.86	0.0416	0.0168	3.5	6,342	7610	282				
34	275.93	4094.29	0.0940	0.0380	4.0	16,377	19653	728				

35	192.85	2285.80	0.0525	0.0212	7.0	16,001	19201	711
36	243.44	3681.55	0.0845	0.0342	7.0	25,771	30925	1,145
37	229.25	2748.96	0.0631	0.0255	6.5	17,868	21442	794
38	362.00	7738.10	0.1776	0.0719	6.0	46,429	55714	2,063
39	284.29	3792.41	0.0871	0.0352	7.0	26,547	31856	1,180
40	274.51	4535.60	0.1041	0.0421	9.0	40,820	48984	1,814
41	300.69	4577.28	0.1051	0.0425	10.5	48,061	57674	2,136
42	258.27	3450.01	0.0792	0.0321	11.0	37,950	45540	1,687
43	174.44	1677.62	0.0385	0.0156	5.5	9,227	11072	410
44	247.59	3695.96	0.0848	0.0343	4.0	14,784	17741	657
45	172.02	1613.37	0.0370	0.0150	11.0	17,747	21296	789
46	129.22	1001.41	0.0230	0.0093	10.0	10,014	12017	445
47	101.53	588.56	0.0135	0.0055	3.0	1,766	2119	78
48	71.88	320.14	0.0073	0.0030	3.0	960	1153	43
49	156.02	1495.79	0.0343	0.0139	3.5	5,235	6282	233
50	193.77	2218.53	0.0509	0.0206	3.0	6,656	7987	296
51	166.88	1711.97	0.0393	0.0159	3.0	5,136	6163	228
52	170.96	1743.25	0.0400	0.0162	6.0	10,460	12551	465
53	228.95	3211.71	0.0737	0.0298	4.5	14,453	17343	642
54	236.62	3386.90	0.0778	0.0315	3.5	11,854	14225	527
55	132.53	846.04	0.0194	0.0079	3.5	2,961	3553	132
56	207.72	2540.85	0.0583	0.0236	3.5	8,893	10672	395
57	121.93	908.21	0.0208	0.0084	4.5	4,087	4904	182
58	157.59	1345.99	0.0309	0.0125	5.0	6,730	8076	299
59	279.45	4168.73	0.0957	0.0387	7.0	29,181	35017	1,297
60	369.63	8517.68	0.1955	0.0791	9.0	76,659	91991	3,407
61	273.87	4412.16	0.1013	0.0410	11.0	48,534	58241	2,157
62	276.01	4064.27	0.0933	0.0378	12.0	48,771	58526	2,168
63	333.26	5520.56	0.1267	0.0513	10.0	55,206	66247	2,454
64	310.35	5761.39	0.1323	0.0535	9.0	51,852	62223	2,305
65	425.73	11035.60	0.2533	0.1025	8.0	88,285	105942	3,924
66	325.93	6363.41	0.1461	0.0591	8.0	50,907	61089	2,263
Unknown	41.93	1.38	0.0000	0.0000		0	0	0
Total			3.9057			1,009,766	1211719	44,878
Cost Estimates								
Estimate A			Estimate B					
Construction Days:	45		Total Treatment Length:	7350 ft				
Cost per Day:	\$5,200		Est. Treat.Cost per foot:	\$35 - \$40				
Permit/Oversight	\$40,000		Est. Treatment Cost:	\$257,000 - 294,000				
Cost Estimate:	\$274,000							

SULPHUR-BARRY RESTORATION PROPOSAL

7/17/2007

Gully Obliteration (Pond-and-Plug)

Plug	Width (ft)	Length (ft)	Area (ft ²)	Depth (ft)	Volume (ft ³)	1.1 X ft ³	Volume (yd ³)
1	50	80	4,000	6	24,000	26,400	978
2	100	50	5,000	8	40,000	44,000	1,630
3	80	160	12,800	12	153,600	168,960	6,258
4	35	65	2,275	7	15,925	17,518	649
5	52	85	4,420	6	26,520	29,172	1,080
6	58	93	5,394	6	32,364	35,600	1,319
6a	16	120	1,920	3	5,760	6,336	235
7	65	60	3,900	8	31,200	34,320	1,271
Total		713	39,709		329,369	362,306	13,419

Pond	Additional Width (ft)	Total Width (ft)	Length (ft)	Area (ft ²)	Pond Volume (yd ³)	Est. Max. Depth (ft)	Volume (ft ³)	Volume (yd ³)
1	20	55	140	7,700	980	8	13,200	489
2	45	80	90	7,200	1630	10	35,200	1,304
3	39	164	80	13,120	6260	12	168,960	6,258
4	37	60	90	5,400	550	9	8,759	324
5	0	70	140	9,800	2550	8	23,345	865
6	10	75	100	7,500	1450	8	38,722	1,434
7	37	117	140	16,380	3175	10	101,820	3,771
Total			780	67,100	16,595		390,006	14,445

Grade-drop Structure


Gradient (ft/ft)	Width (ft)	Length (ft)	Top Depth (ft)	Average Depth (ft)	Soil Volume X 1.1 (ft ³)	Volume Soil (yd ³)	Volume Rock (yd ³)
0.04*	60	325	12	6	67,500	2,750	2,300

*Elevation Difference Between Top and Bottom = 12 ft


Gradient = 12 ft / 325 ft = 0.0369 ft/ft

240 boulders of 3-ft diameter (1-ft drop per boulder structure)


Top Grade-Control XS (7/3/07)
ec cell = 1.0 ft²



Bottom Grade-Control XS (7/3/07)
ec cell = 1.0 ft²



Grade-Control XS on Sulphur Cr (7/3/07)
ec cell = 1.0 ft²



SULPHUR-BARRY RESTORATION PROPOSAL GRADE-DROP STRUCTURE

7/17/2007

Barry Creek Entrenchment

1. Upstream Cross-section

Station (ft)	Elevation (ft)	Rod (ft)	Remarks
0	88.8	11.2	Left TET
1	80.1	19.9	TOT
44	83.2	16.8	
61	82.7	17.3	TOT
75	88.6	11.4	Right TET

2. Middle Width = 60 ft

3. Bottom Cross-section

Station (ft)	Elevation (ft)	Rod (ft)	Remarks
0	98.4	1.6	Left TET
2	87.9	12.1	TOT
10	88	12	
15	89.7	10.3	
43	90.9	9.1	TOT
53	94.3	5.7	Right TET

Sulphur Creek Entrenchment

4. XS Immediately downstream of Confluence

Station (ft)	Elevation (ft)	Rod (ft)	Remarks
0	96.2	3.8	Left TET (berm?)
6	91.7	8.3	Mid-terrace
15	88.3	11.7	TOT
58	88.7	11.3	TOT
64	93.8	6.2	Right TET

Summary

XS	Width (ft)	Depth (ft)	Area (ft ²)
1	53	6.8	360
2	60		
3	53	5.2	276
4	64	5.3	339
Average	57.5	5.8	332

$$332 \text{ ft}^2 \times 0.5 = 166$$

$$166 \text{ ft}^2 \times 1.1 = 182$$

Structure Length = 325-ft

Average Structure Depth = $5.8/2 = 2.9$ -ft

Structure Volume = 57.5-ft wide X 325-ft long X 2.9-ft deep = 54,194-ft³ (2,007-yd³)

SULPHUR - BARRY RESTORATION PROPOSAL BUDGET ESTIMATE

Jan-08

Item	Volume (yd ³)	Construction Days	Construction Hours
Soil Plugs	13,419	11	89
Grade-drop soil	2,800	2	19
rock	2,700	5	40
boulders	290	3	24
Subtotal		22	172
Vegetation Planting		5	40
Total		27	212

Equipment	Hours	Cost/Hour	Total Cost
Excavator	172	\$200.00	\$34,425.33
Loader	172	\$200.00	\$34,425.33
Dozer	108	\$150.00	\$16,219.00
Water Truck	148	\$120.00	\$17,775.20
Hand Crew*	40	\$400.00	\$16,000.00
Total			\$118,844.87

* 4 people at \$50.00/hour = \$400/hour.

Rock Purchase and Haul @ \$45/yd ³ =	\$121,500.00
Boulder Purchase and Haul @ \$45/yd ³ =	\$13,050.00
Total =	\$134,550.00

Total Implementation Cost = **\$253,394.87**

BEAR VALLEY MEADOW RESTORATION BUDGET

Feb-08

Work Item	Estimated Cost
Field Work & Site Surveys	\$3,000.00
NEPA/CEQA	\$0.00
Permit Acquisition	\$5,000.00
Project Design & Engineering	\$2,000.00
Contract Preparation	\$1,000.00
Contract Administration	\$5,000.00
Contract Cost	\$400,000.00
Materials & Supplies	\$1,000.00
Monitoring	\$3,000.00
Other	\$0.00
Total	\$420,000.00

APPENDIX F


FLOOD FREQUENCY ANALYSES

ESTIMATED FLOOD FREQUENCIES									
		Comparing Gaged Watersheds to Ungaged Watersheds							
		From MAGNITUDE AND FREQUENCY OF FLOODS IN CALIFORNIA							
		by A.O. Waananen and J.R. Crippen, June 1977, USGS Water-Resources Investigations 77-21							
Watershed	Drainage Area (mi ²)	Gage Number	Peak Discharge (cfs) at indicated recurrence intervals						
Name			2 yr	5 yr	10 yr	25 yr	50 yr	100 yr	
Cottonwood Creek	7.08	11391423	42	84	122	181	235	297	
Peak Flow/mi ²	1.00		6	12	17	26	33	42	
			(^{0.88})	(^{0.82})	(^{0.80})	(^{0.79})	(^{0.78})	(^{0.77})	
		(A _u /A _g)							
Antelope Valley Cr	11.40		64	124	179	264	341	429	
Bear Valley Cr	18.50		98	185	263	387	497	622	
Bear Valley Trib.	3.90		25	52	76	113	148	188	

APPENDIX G
BEAR VALLEY SURVEYS


Bear Valley Meadow Longitudinal Profile

5/29/2007 (slope = 0.02 ft/ft)



BEAR VALLEY MEADOW, LONGITUDINAL PROFILE				
			5/29/2007	
Station (ft)	Elevation (ft)	Rod, Adjusted (ft)	Bearing (°)	Remarks
0	5237.6	9.0	352	LTET, XS-5
105	5236.1	10.5	352	Single thread entrenchment
152	5235.2	11.4	18	
263	5232.7	13.9	360	
360	5230.1	16.5	360	Left side slope, aggraded reach and end of entrenchment
587	5225.0	21.6	350	Top of headcut reach
682	5221.8	24.8	6	LTET (near spring)
800	5218.8	27.8	358	LTET
924	5215.2	31.4	360	Top of short, aggraded reach
991	5212.8	33.8	360	LTEB, XS-3 (on ATV crossing)
1022	5211.8	34.8	360	LTET @ 4-ft headcut and narrow trench
1092	5209.2	37.4	360	RTET, top of fan. Floodplain all on right side.
1187	5209.3	37.3	360	On floodplain between channels
1314	5206.8	39.8	360	On floodplain between channels, XS-4
1474	5200.7	45.9	360	Top of section where the two channels merge
1571	5198.8	47.8	316	Merge zone
1622	5198.9	47.7	284	Turning point
1650	5197.4	49.2	344	RTET
1666	5196.8	49.8	344	Bottom of proposed upper project reach
1814	5194.5	52.1	344	Top of gravel deposit
1834	5194.4	52.2	344	On floodplain between channels
1900	5192.6	54.0	250	Turning point
1929	5192.1	54.5	328	On floodplain between channels
2190	5187.0	59.6	352	On floodplain between channels
2381	5181.3	65.3	330	On floodplain between channels
2643	5175.9	70.7	330	RTET, right channel & at fence
2885	5172.0	74.6	330	RTET, convergence of the two channels. 3rd channel to right
3210	5165.2	81.4	344	RTET, main gully & near divergence of the two gullies
3432	5162.2	84.4	324	RTET, main gully & next to 4-ft headcut
3555	5160.2	86.4	324	RTET, XS-6
3750	5156.8	89.8	322	RTET, main gully
3960	5152.8	93.8	320	RTET, main gully
4059	5150.6	96.0	320	RTET, XS-7
4300	5146.9	99.7	320	RTET, main gully
4378	5145.3	101.3	264	RTET, main gully
4450	5144.5	102.1	290	RTET, main gully
4553	5143.7	102.9	332	RTET, main gully
4675	5142.1	104.5	350	RTET, main gully
4762	5140.3	106.3	350	RTET, XS-2
5000	5135.4	111.2	350	RTET, main gully
5148	5132.3	114.3	324	LTET, main gully & cnfl w/ L-side channel over a 5-ft headcut
5365	5129.1	117.5	346	LTET & cnfl w/ far right channel (valley cross-over)
5644	5121.9	124.7	320	LTET, main gully
5799	5119.8	126.8	320	Cnfl w/ unnamed Bear Vally Creek over a 5-ft headcut
5863	5120	126.6	354	LTET, XS-1 & next to community well
6228	5113.2	133.4	2	LTET, main gully
6666	5104.9	141.7	356	LTET, main gully
6810	5102.2	144.4	356	LTET, main gully, XS-8
7100	5097.6	149.0	8	LTET, main gully
7289	5093.6	153.0	8	LTET, main gully
7430	5089.7	156.9	6	LTET, above confluence with main remnant channel, left-side
7484	5090.0	156.6	60	LTET, below confluence with main remnant over a 6-ft headcut
7630	5087.3	159.3	360	RTET, XS-9 . Valley shifts to right side
7777	5085.0	161.6	360	Right-side floodplain
7878	5082.3	164.3	360	Right-side floodplain (historic Smithneck floodplain)
7930	5081.9	164.7	360	Right-side floodplain & toe of road
7939	5087.5	159.1		Edge of road pavement

Cross Section #1



Cross Section #1

Location: Bear Valley Creek

Description: Well Station


Survey Date: 05/21/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	5.1	0.0	Left Pin, Wire fence next to Rd
50	6.4	-1.3	
63	6.5	-1.4	Top Edge Bank
68	6.9	-1.8	Top Of Bank
71	7.0	-1.9	Top Of Bank
74	6.7	-1.6	Top Edge Bank
100	6.0	-0.9	
152	6.2	-1.1	Top Edge Bank
158	6.6	-1.5	Top Of Bank
160	6.6	-1.5	Top Of Bank
170	6.4	-1.3	Top Edge Bank
200	6.4	-1.3	Trail
227	6.1	-1.0	
256	6.5	-1.4	Top Edge Bank
268	8.0	-2.9	Top Of Bank
272	8.1	-3.0	Top Of Bank
274	7.4	-2.3	Top Edge Bank
278	7.7	-2.6	Toe of Terrace
282	6.9	-1.8	Top Edge Terrace
296	6.8	-1.7	Top Edge Terrace
313	8.1	-3.0	Top Edge Slope
320	13.6	-8.5	Toe Of Slope
330	13.5	-8.4	Top Edge Bank
332	14.6	-9.5	Left Edge Water
334	15.3	-10.2	Thalweg
340	14.6	-9.5	Right Edge Water, Toe Of Terrace
349	8.6	-3.5	Top Edge Terrace
372	8.1	-3.0	Top Edge Bank
374	9.4	-4.3	Top Of Bank
377	9.4	-4.3	Top Of Bank
381	8.5	-3.4	Top Edge Bank
399	8.1	-3.0	Edge Of Riparian (Rose)
412	8.5	-3.4	Remnant
472	7.5	-2.4	Edge Of Historic Floodplain, Toe Of Terrace
494	5.3	-0.2	
570	5.1	0.0	Right Pin

= 5.1-Rod Height

Cross Section #2



Cross Section #2

Location: Bear Valley Creek

Description: Between Well and Ridge


Survey Date: 05/21/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	5.4	0.0	Left Pin
32	6.2	-0.8	
88	6.4	-1.0	Top Edge Terrace
94	7.1	-1.7	
105	10.9	-5.5	Toe of Terrace
114	11.0	-5.6	Top Edge Bank
116	11.6	-6.2	Left Edge Water
116	11.8	-6.4	Top of Bank
124	11.6	-6.2	Right Edge Water
125	11.7	-6.3	Top of Bank
126	11.1	-5.7	Top Edge Bank
127	10.8	-5.4	Toe of Terrace
136	6.2	-0.8	Top Edge Terrace
197	6.2	-0.8	Top Edge Terrace
210	13.4	-8.0	Toe of Terrace
222	14.4	-9.0	Top Edge Bank
223	14.4	-9.0	Left Edge Water
230	15.2	-9.8	Thalweg
233	14.4	-9.0	Right Edge Water, Toe of Terrace
245	6.2	-0.8	Top Edge Terrace
343	4.9	0.5	
374	5.3	0.1	
383	6.0	-0.6	
393	6.3	-0.9	Top Edge Bank
396	6.8	-1.4	Top of Bank
398	6.8	-1.4	Top of Bank
400	6.3	-0.9	Top Edge Bank
408	6.3	-0.9	Top Edge Bank
417	7.0	-1.6	Top of Bank
424	7.0	-1.6	Top of Bank
428	6.5	-1.1	Top Edge Bank
500	5.1	0.3	
528	4.6	0.8	
533	4.0	1.4	
542	4.2	1.2	Top Edge Deposits
554	7.0	-1.6	Top of Deposit Slope
564	3.9	1.5	
627	3.8	1.6	Top Edge Bank
629	4.4	1.0	Thalweg
634	4.0	1.4	Top Edge Bank
655	3.5	1.9	
707	3.7	1.7	Top Edge Bank
710	5.2	0.2	Top of Bank
716	5.2	0.2	Top of Bank
720	4.3	1.1	Top Edge Bank
899	0.6	4.8	Right Pin

= 5.4-Rod Height

Cross Section #2A



Cross Section #2A

Location: Bear Valley Creek

Description: Unnamed Tributary


Survey Date: 05/21/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	1.4	0.0	Left Pin
25	5.0	-3.6	Top of Slope
40	4.2	-2.8	
66	4.7	-3.3	
71	5.3	-3.9	Top Edge Terrace
85	8.2	-6.8	Toe of Terrace
88	8.8	-7.4	Top Edge Bank
89	9.2	-7.8	Left Edge Water
90	9.6	-8.2	Thalweg
92	9.2	-7.8	Right Edge Water
93	8.8	-7.4	Top Edge Bank
94	9.3	-7.9	Toe of Terrace
100	4.6	-3.2	Top Edge Terrace
118	4.4	-3.0	Top Edge Terrace
126	6.5	-5.1	Toe of Terrace
163	7.0	-5.6	Top Edge Bank
167	7.8	-6.4	Top of Bank
169	7.8	-6.4	Top of Bank
172	6.9	-5.5	Top Edge Bank
239	7.0	-5.6	Toe of Terrace
248	5.0	-3.6	Top Edge Terrace
290	4.8	-3.4	
342	5.4	-4.0	Right Pin, Cross Section #2 Left Pin

= 1.4-Rod Height

Cross Section #3



Cross Section #3

Location: Bear Valley Creek

Description: Across from Archeological site


Survey Date: 05/23/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Corr. Rod Height_1 (ft)	Corr. Rod Height_2 (ft)	Relative Height (ft)	Remarks
0	5.3			0	Right Pin, next to rutting Rd.
50	8.1			-2.8	
100	11.0			-5.7	
120	12.1			-6.8	Toe of Slope
136	12.3			-7.0	Top Edge Bank
143	12.8			-7.5	Top of Bank
184	13.3			-8.0	Top of Bank
190	13.0			-7.7	Top Edge Bank
203	12.8			-7.5	Top Edge Terrace
205	14.0			-8.7	Toe of Terrace
215	13.4			-8.1	Toe of Terrace
218	13.1			-7.8	Top Edge Terrace
250	13.6			-8.3	Top Edge Terrace, Begin Willow Thicket
256	14.1			-8.8	Toe of Terrace
274	14.5			-9.2	Top Edge Bank
275	15.0			-9.7	Top of Bank
283	15.0			-9.7	Top of Bank
287	14.7			-9.4	Top Edge Bank
308	14.7			-9.4	Top Edge Bank
310	14.9			-9.6	Top of Bank
315	14.7			-9.4	Top of Bank
317	14.3			-9.0	Top Edge Bank
360	14.3			-9.0	Top Edge Terrace
361	15.5			-10.2	Toe of Terrace
373	15.4			-10.1	Toe of Terrace
374	14.8			-9.5	Top Edge Terrace
374	3.0	14.8		-9.5	TURNING POINT
410	2.7	14.5		-9.2	
431	3.2	15.0		-9.7	Top Edge Bank
440	4.1	15.9		-10.6	Top of Bank
451	4.0	15.8		-10.5	Top of Bank
456	3.6	15.4		-10.1	Top Edge Bank
465	3.2	15.0		-9.7	End of Gravel Deposit
480	3.2	15.0		-9.7	
480	11.3		15.0	-9.7	TURNING POINT
494	11.1		14.8	-9.5	End of Gravel Levee
497	10.9		14.6	-9.3	
502	10.7		14.4	-9.1	
508	11.2		14.9	-9.6	End of Levee and Willow Thicket
512	11.6		15.3	-10.0	Top Edge Bank
513	12.3		16.0	-10.7	Top of Bank
514	13.1		16.8	-11.5	
515	13.3		17.0	-11.7	
520	12.9		16.6	-11.3	Left Edge Water, Top of Bank
522	11.9		15.6	-10.3	Top Edge Bank
540	11.1		14.8	-9.5	
560	10.1		13.8	-8.5	
575	8.9		12.6	-7.3	End of grass and sage
606	5.5		9.2	-3.9	Left Pin

$$= 5.3 - \text{Rod Height} = B35 + (\$B\$33 - \$B\$34) = D42 - (B42 - B43)$$

Cross Section #4



Cross Section #4

Location: Bear Valley Creek


Description:

Survey Date: 05/23/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	9.7	0	Left Pin
16	15.2	-5.5	Toe of Slope, Edge of High Flow Line
23	17.2	-7.5	Top Edge Bank
26	18.1	-8.4	Left Edge Water
28	19.0	-9.3	Thalweg
31	18.1	-8.4	Right Edge Water, Toe of Terrace, Edge of Gravel Deposit
36	15.3	-5.6	Top Edge Terrace, Edge of Willow
52	15.7	-6.0	Top Edge Bank
58	15.9	-6.2	Top of Bank
60	15.9	-6.2	Top of Bank
65	14.3	-4.6	Top Edge Bank
72	14.1	-4.4	Top Edge Gravel Deposit
77	14.1	-4.4	Top Edge Gravel Deposit
84	15.5	-5.8	Toe of Gravel Deposit, Edge of Willow
88	15.9	-6.2	Top of Bank
91	14.9	-5.2	Top Edge Bank
100	14.8	-5.1	
130	13.6	-3.9	
169	13.6	-3.9	
200	13.6	-3.9	
222	13.5	-3.8	
234	14.0	-4.3	remnent
237	13.6	-3.9	Top Edge Bank, Edge of Willow
246	15.0	-5.3	Top of Bank
275	15.0	-5.3	Top of Bank
275	16.0	-6.3	
281	15.5	-5.8	Top Edge Bank
287	15.0	-5.3	
290	14.8	-5.1	
296	14.9	-5.2	Top Edge Bank, Edge of Willow/Sedge
297	15.2	-5.5	Top of Bank
302	14.9	-5.2	Top Edge Bank
318	14.1	-4.4	
323	14.2	-4.5	Top Edge Bank
327	14.5	-4.8	Thalweg
333	14.0	-4.3	Top Edge Bank
365	13.7	-4.0	
414	13.7	-4.0	
432	14.3	-4.6	Top Edge Bank
442	15.3	-5.6	Top of Bank
448	14.9	-5.2	Top of Bank
456	13.9	-4.2	Top Edge Bank
461	13.8	-4.1	
467	13.7	-4.0	Toe of Slope
600	11.0	-1.3	Right Pin

Cross Section #5



Cross Section #5

Location: Bear Valley Creek


Description: Lower Metal Bridge, Archery Park

Survey Date: 05/23/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	5.0	0	Left Pin
27	6.8	-1.8	Edge of Old Rd
34	7.8	-2.8	
42	8.1	-3.1	
56	9.2	-4.2	Top Edge Bank
63	11.0	-6.0	Top of Bank, Toe of Slope
73	9.8	-4.8	Top Edge Bank
98	9.6	-4.6	
105	8.4	-3.4	
138	8.3	-3.3	
147	10.1	-5.1	
189	10.3	-5.3	Top Edge Terrace
199	13.3	-8.3	Left Edge Water, Toe of Terrace
200	13.8	-8.8	
205	13.8	-8.8	
208	13.8	-8.8	Right Edge Water, Toe of Terrace
220	9.7	-4.7	Top Edge Terrace
233	8.1	-3.1	
245	7.6	-2.6	Right Pin

Cross Section #6



Cross Section #6

Location: Bear Valley Creek


Description: Downstream of convergence section

Survey Date: 05/25/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	4.8	0	Left Pin
25	9.9	-5.1	Toe of Slope
50	10.5	-5.7	
100	10.2	-5.4	
139	9.7	-4.9	Top Edge Terrace
143	11.6	-6.8	Top Edge Bank
144	13.1	-8.3	Top of Bank
146	13.5	-8.7	Left Edge Water
149	13.5	-8.7	Right Edge Water, Top of Bank
151	12.2	-7.4	Top Edge Bank
158	10.2	-5.4	Top Edge Terrace
162	9.8	-5.0	
226	10.1	-5.3	
230	9.4	-4.6	
242	9.6	-4.8	
262	10.0	-5.2	Top Edge Terrace
266	12.0	-7.2	Toe of Terrace
278	13.2	-8.4	Top Edge Terrace (mid)
282	14.6	-9.8	Top Edge Bank
283	17.1	-12.3	Top of Bank
285	17.2	-12.4	Left Edge Water
288	17.6	-12.8	
289	17.8	-13.0	Thalweg
290	17.5	-12.7	
290	17.2	-12.4	Right Edge Water, Toe of Terrace
294	12.7	-7.9	Top Edge Terrace (mid)
298	12.5	-7.7	Toe of Terrace
308	9.2	-4.4	Top Edge Terrace
320	9.3	-4.5	
329	9.6	-4.8	Top Edge Terrace
333	10.3	-5.5	Toe of Slope
337	9.7	-4.9	Top Edge Terrace
356	9.7	-4.9	Top Edge Terrace
361	12.0	-7.2	Toe of Terrace
365	11.5	-6.7	Toe of Terrace
373	9.2	-4.4	Top Edge Terrace
400	8.8	-4.0	
423	8.6	-3.8	Top Edge Bank
427	9.5	-4.7	Top of Bank
430	8.7	-3.9	Top Edge Bank
449	8.6	-3.8	
464	9.3	-4.5	Top Edge Bank
466	9.9	-5.1	Top of Bank
471	10.1	-5.3	Top of Bank
473	9.3	-4.5	Top Edge Bank, Toe of Slope
478	9.1	-4.3	
500	8.0	-3.2	
550	5.8	-1.0	
575	4.8	0.0	Right Pin

Cross Section #7



Cross Section #7

Location: Bear Valley Creek


Description: Near End of Spur Ridge

Survey Date: 05/25/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	5.4	0	Left Pin
15	10.3	-4.9	Toe of Slope
18	10.5	-5.1	Top Edge Terrace
24	12.6	-7.2	Toe of Terrace
34	12.5	-7.1	Top Edge Bank
36	13.8	-8.4	Top of Bank
37	14.0	-8.6	Thalweg
38	13.8	-8.4	Right Edge Water, Top of Bank
39	13.3	-7.9	Top Edge Bank
42	13.1	-7.7	Toe of Terrace
48	11.0	-5.6	Top Edge Terrace
52	10.5	-5.1	
78	10.8	-5.4	Toe of Terrace
85	10.4	-5.0	Top Edge Terrace
98	9.7	-4.3	
104	10.2	-4.8	
133	10.5	-5.1	Top Edge Terrace
137	11.2	-5.8	Toe of Terrace
150	11.0	-5.6	
180	11.1	-5.7	Top Edge Bank
188	11.9	-6.5	Top of Bank
191	11.8	-6.4	Top of Bank
194	11.4	-6.0	Top Edge Bank
203	9.7	-4.3	Top Edge Terrace
208	9.4	-4.0	
226	9.7	-4.3	
250	9.7	-4.3	
268	10.2	-4.8	
288	9.8	-4.4	Top Edge Terrace
296	16.2	-10.8	Toe of Terrace
297	16.4	-11.0	Left Edge Water
298	17.2	-11.8	
304	17.1	-11.7	
305	16.4	-11.0	Right Edge Water
305	16.3	-10.9	Top Edge Bank
319	15.7	-10.3	
325	15.6	-10.2	Toe of Terrace
340	9.8	-4.4	Top Edge Terrace
374	9.8	-4.4	
392	10.1	-4.7	
404	10.2	-4.8	Top Edge Bank
405	10.8	-5.4	Top of Bank
407	10.8	-5.4	Top of Bank
408	10.5	-5.1	Top Edge Bank
418	10.0	-4.6	
442	10.2	-4.8	
456	10.4	-5.0	
471	11.0	-5.6	Top Edge Terrace
475	12.6	-7.2	Toe of Terrace, Top of Bank
476	12.6	-7.2	Top of Bank
478	12.2	-6.8	Top Edge Bank
483	11.7	-6.3	
491	11.1	-5.7	Toe of Terrace
493	10.4	-5.0	Top Edge Terrace
509	9.8	-4.4	
525	9.9	-4.5	
542	10.7	-5.3	
560	10.7	-5.3	Top Edge Bank
562	11.2	-5.8	Top of Bank
565	11.3	-5.9	
567	11.2	-5.8	Top of Bank
567	10.7	-5.3	Top Edge Bank
583	10.3	-4.9	
623	9.7	-4.3	
658	8.3	-2.9	
691	7.2	-1.8	
702	6.4	-1.0	
742	5.6	-0.2	Right Pin (base of Lone Willow)


Cross Section #8



Cross Section #8
Location: Bear Valley Creek
Description: Near End of Spur Ridge
Survey Date: 05/25/2007
Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	4.9	0	Left Pin (Above Antelope Valley Rd)
15	10.1	-5.2	Toe of Slope, Inside Ditch
18	9.1	-4.2	Left Edge Road
32	9.1	-4.2	Right Edge Road
47	9.3	-4.4	
58	10.2	-5.3	Fence
94	9.9	-5.0	
107	9.8	-4.9	
124	10.4	-5.5	
134	10.3	-5.4	
142	10.7	-5.8	
149	10.3	-5.4	
176	10.0	-5.1	
192	10.5	-5.6	
203	10.8	-5.9	
213	11.6	-6.7	Top Edge Bank
215	12.0	-7.1	Top of Bank
216	12.1	-7.2	Thalweg
216.5	12.0	-7.1	Top of Bank
217	11.7	-6.8	Top Edge Bank
220	11.2	-6.3	
243	11.4	-6.5	
249	10.9	-6.0	
253	11.3	-6.4	
256	11.3	-6.4	Top Edge Bank
258	11.8	-6.9	Top of Bank
259	11.6	-6.7	Top of Bank
260	11.5	-6.6	Top Edge Bank
279	11.1	-6.2	
290	10.8	-5.9	Top Edge Bank
295	11.0	-6.1	Top of Bank
299	11.3	-6.4	
301	11.3	-6.4	Top of Bank
304	11.1	-6.2	Top Edge Bank
313	10.8	-5.9	
316	10.8	-5.9	
321	11.0	-6.1	
335	10.9	-6.0	
353	11.1	-6.2	
361	10.9	-6.0	
376	11.3	-6.4	
383	11.4	-6.5	
390	11.2	-6.3	
393	10.7	-5.8	
396	10.8	-5.9	
403	11.2	-6.3	
406	11.0	-6.1	
421	11.1	-6.2	
443	11.3	-6.4	
450	11.2	-6.3	Top Edge Terrace
457	18.8	-13.9	Toe of Terrace
462	18.9	-14.0	Top Edge Bank
466	20.3	-15.4	
468	20.9	-16.0	
469	21.3	-16.4	Left Edge Water
469	21.5	-16.6	
471	21.8	-16.9	Thalweg
474	21.3	-16.4	Right Edge Water
480	19.8	-14.9	Top Edge Bank
486	18.8	-13.9	Toe of Terrace
501	11.1	-6.2	Top Edge Terrace
513	10.7	-5.8	Toe of Slope
521	9.3	-4.4	
545	7.4	-2.5	Right Pin (base of burnt cedar stump)

Cross Section #9



Cross Section #9

Location: Bear Valley Creek

Description: Immediately upstream of The Coyce House

Survey Date: 05/25/2007

Surveyor: Terry Benoit

Stake Dist (ft)	Rod Height (ft)	Relative Height (ft)	Remarks
0	4.1	0	Left Pin (on fan)
30	4.7	-0.6	
60	5.2	-1.1	
116	5.9	-1.8	
141	7.7	-3.6	
174	8.2	-4.1	Toe of Fan
183	8.9	-4.8	
202	8.2	-4.1	
212	8.0	-3.9	Top Edge Rip Rap Bank
246	14.6	-10.5	Toe of Rip Rap Slope
250	15.1	-11.0	
265	14.6	-10.5	Top Edge Gravel Bar
270	16.6	-12.5	Left Edge Water
272	17.3	-13.2	
278	16.6	-12.5	Right Edge Water, Top of Bank
280	16.1	-12.0	Top Edge Bank
288	15.2	-11.1	Toe of Terrace
296	9.8	-5.7	Top Edge Terrace
313	9.6	-5.5	
341	10.0	-5.9	Toe of Slope
347	8.8	-4.7	
363	5.1	-1.0	Right Pin

APPENDIX H

Impact Avoidance and Minimization Measures

APPENDIX H. IMPACT AVOIDANCE AND MINIMIZATION MEASURES

ANTELOPE VALLEY WILDLIFE AREA (AVWA) AND SMITHNECK CREEK WILDLIFE AREA (SCWA) LAND MANAGEMENT PLAN (LMP) WATERSHED RESTORATION PROGRAM

The proposed watershed restoration program has been designed to include several protection measures to avoid or minimize potential adverse environmental effects. The following biological and water quality conservation measures will be used during the course of program implementation.

BIOLOGICAL RESOURCE CONSERVATION

The following measures will be implemented to minimize potential adverse effects to sensitive biological resources:

1. In order to avoid potential construction-related impacts to nesting birds and fawning deer in the project vicinity, or to aquatic species that may occur within the stream corridors, construction will occur between September 1 and October 1.

Alternatively, construction may begin after June 1 following consultation with Department and USFS wildlife biologists, if a qualified biologist verifies that no birds are nesting in vegetation to be removed, that no raptors or yellow warblers nesting in the project vicinity would be subject to nest failure as a result of construction disturbance, and that no mule deer fawns in their “hiding” phase would be displaced by construction disturbance. Construction may continue after October 1 if it is determined, in consultation with a Department aquatic biologist, a USFS aquatic biologist, and the Central Valley RWQCB, that sensitive fish species are not present or would not be susceptible to the specific construction disturbance proposed to occur after October 1, and that construction best management practices (BMPs) implemented to protect water quality are adequate protection against potential erosive impacts of winter storm events.

2. Before project construction, fish translocation activities will be conducted to remove all native and game (e.g., brown trout) fish species from the immediate construction area.
 - Block nets will be placed upstream and downstream of the designated construction area to prevent fish from entering the site. The block nets will be placed across the channel approximately 100-feet above and below the designated construction area.
 - Once the construction area has been isolated, electrofishing will be employed throughout the entire length of the construction area to capture, remove, count, and release fish. Electrofishing

passes will be made as necessary until it has been determined by a qualified aquatic biologist that all fish that practicably can be removed have been removed.

- All captured fish will be placed in 5-gallon buckets with fresh, clear water and transported to upstream release sites(s) identified before initiating translocation activities. Buckets containing native fishes will be moved to the release site frequently, with no more than 200 fish in a bucket at one time and for no longer than 15 minutes. All native and/or game fish species will be released in pools or slow moving currents (i.e., glides) and will be allowed to swim out of the buckets. Nonnative and non-game fish and other nonnative aquatic species (e.g., bullfrog tadpoles) will be destroyed. A minimum of one representative bucket sample from the entire translocation effort will be counted for total individuals by species. Any potential fish mortalities will also be noted.
 - Once all fish have been captured, transported, and released, the on-site fisheries biologist will clear the site for construction. During the construction activities, the on-site fisheries biologist will monitor the construction area reaches (with fish removal and transporting equipment) for areas that may become dewatered and potentially strand any fish that may have been missed. Any stranded fish will be immediately captured, transported and released upstream as described above.
 - After completion of field activities, a written letter report documenting activities will be prepared. The letter report will include a description of all fish translocation and salvage activities and estimates for total fish translocated and salvaged by species (including any mortalities).
3. Grade control structures will be designed and constructed to provide passage for all native and desirable game fish species. Grade control structures will be designed utilizing natural materials (e.g., boulders) in a rock ramp and/or step pool configuration. Height of the drop structures and length and depth of pools will be designed to facilitate upstream and downstream passage for multiple fish species and will be based on the swimming abilities of the native and game fish species present in the creeks. The new alignment of the creeks will be hydrologically continuous and provide riffle-pool habitats with a riparian corridor. The new alignment of the creek will provide habitat functions to support a diverse community of species and meet habitat requirements for all necessary life stages (e.g., spawning and rearing).
 4. Structure (e.g. large woody debris) may be installed in restored channels to enhance fish habitat following watershed restoration activities. Riparian vegetation (e.g. willow stakes) may be planted or transplanted along stream banks to enhance riparian habitat following watershed restoration activities. Conifers that are out-competing young aspens may be removed to enhance riparian habitat.

5. Before restoration actions and during the appropriate blooming/identification period, a qualified botanist will conduct surveys in all restoration areas for the presence or absence of special-status plants that might be present in the region (see LMP Table 3.3-3). If individuals or populations of special-status plants are found, they will be avoided to the greatest extent practicable. If avoidance is not feasible and if the particular plant species has any federal or state protection status, additional protection measures will be implemented. These may include transplanting individuals of the affected species, or collecting seed and creating populations elsewhere. These additional protection measures will be developed and approved by a Department, USFS, and/or USFWS biologist, as appropriate depending on the plant's listing status.
6. Before restoration actions, surveys will be conducted for invasive plant species (such as woolly mullein and perennial pepperweed) within the restoration area and in adjacent floodplain areas that may experience a change in hydrology. If any invasive plant species are found, they will be removed or eradicated. No herbicides will be used on USFS property.
7. Before transport to the work sites all construction equipment should be thoroughly washed (steam cleaned) to remove unwanted seeds

WATER QUALITY CONSERVATION

BMPs will be implemented in accordance with applicable federal and state regulations that provide for the protection of water quality at all restoration sites. Before the start of any construction work, clearing, site grading or stockpiling associated with preparation of the sites, measures to control soil erosion, sedimentation, and waste discharges of construction-related contaminants will be identified and installed. USFS and DFG will require all contractors conducting work at the sites to implement these measures, and the general contractor(s) and subcontractor(s) conducting the work will be responsible for constructing or implementing, regularly inspecting, and maintaining the measures in good working order.

Standard erosion control measures (e.g., management, structural, and vegetative controls) will be implemented for all construction activities that expose soil. Grading operations will be conducted to eliminate direct routes for conveying potentially contaminated runoff to new and existing drainage channels. Erosion control barriers such as silt fences/curtains and mulching material will be installed, and disturbed areas will be reseeded with grasses or other plants where necessary. Tracking controls will be required year-round, as needed, to reduce the tracking of sediment and debris from the construction site. The following specific BMPs will be implemented:

A Storm Water Pollution Prevention Plan will be prepared and submitted to the Central Valley RWQCB. It will identify BMPs that will be used to eliminate or minimize the potential for construction-related pollution (e.g. sediment, fuels, pesticides, cement) to enter stream flows directly, or through stormwater runoff. All BMPs will be implemented accordingly.

- ▶ All work will be conducted according to site-specific construction plans that identify areas for clearing and grading so that ground disturbance is minimized. Sensitive habitats to be avoided will be identified with orange fencing or other similar demarcation.
- ▶ A point of entrance/exit to the construction sites will be identified to reduce the tracking of mud and dirt onto public roads by construction vehicles, and each construction entrance/exit will be graded and stabilized to prevent runoff from leaving the construction site. All runoff from stabilized entrances/exits will be routed through a sediment-trapping device before discharge. At a minimum, entrances and exits shall be inspected daily, and controls implemented as needed.
- ▶ Stream flows that do not dissipate into the historic flood plain during restoration will be diverted around the restoration area as needed to avoid erosion and sedimentation while construction is occurring.
- ▶ Stream flows will be diverted around construction activities during the dry season as necessary to avoid infringing upon downstream water appropriations.
- ▶ Sediment control BMPs will be installed at the downstream extent of the restoration areas to capture any sediments released during construction. These BMPs will be maintained at least through the first flush of the restored area to capture any sediments that may be eroded from newly restored habitats.
- ▶ Stockpiles will be covered and protected from exposure to erosion and flooding.
- ▶ Disturbed soils will be stabilized before the onset of the winter season.

BMPs will also specify appropriate hazardous materials handling, storage, and spill response practices to reduce the possibility of adverse impacts from use or accidental spills or releases of contaminants. Specific measures that will be applied to the restoration program include, but are not limited to, the following:

- ▶ Onsite handling rules will be developed and implemented to keep construction and maintenance materials out of drainages and waterways.

- ▶ All refueling and servicing of equipment will be conducted with absorbent material or drip pans underneath to contain spilled fuel. Any fluid drained from machinery during servicing will be collected in leak-proof containers and delivered to an appropriate disposal or recycling facility.
- ▶ All construction staging and fueling areas will be located at least 100 feet away from stream channels or wetlands to minimize accidental spills and runoff of contaminants.
- ▶ Spill cleanup equipment will be maintained in proper working condition. All spills will be cleaned up immediately according to a spill prevention and response plan prepared for the restoration program. Appropriate resource agencies (e.g., USFS, DFG, RWQCB) will be notified immediately of any spills and cleanup procedures.